BRUHAT BANAGLORE MAHANAGARA PALIKE

Yelahanka Satellite Town Sub Division

EIRL

Agency :M/s. Ram and Company, Prop.Sri C R Girish, No:12, Patel Pillegowda Layout, Ramachandrapura, Bangalore-560013

Sl No	Item Of Work	Unit	Estimate qty	Rate	Amount (Rs.)	Whether the item alternative in tender or additional items	Whether the extra item is included in sanctioned estimate	How the Cost is proposed to be met	Whether extra item is included in S.R.	Remarks
1	2	3	4	5	6	7	8	9	10	11
E1	Construction of Granular Sub-Base of required grading as per design mixing in a mechanical mix plant at OMC, carriage of mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per clause 401 (For Grading -V Material) (PWD SR 21-22 Vol III Pg no 19 Item No 4.1 A (v))	Cum	1405.30	2607.52	3664345.00	Additonal Item	No	Savings in Estimate	Yes	
	TOTAL EIRL AMOUNT				3664345.00					
	AMOUNT IN WORDS	Rupees Thirty Six lakh Sixty Four Thousand Three Hundred Forty Five Only								

PERCENTAGE OF EXCESS OVER AMOUNT PUT TO TENDER

EIRL Approved Tender Price = 3664345.00 / 169388949.00 x100 = 2.16 %

10.06.2022
Asst Engineer

10/6/2022
Asst.Executive Engineer

10/6/22
Executive Engineer

...tegory	Other
Period of Completion	12 Month

Scanned by CamScanner